




V502, EDITION 4

Prepared by the U.S. Army Topographic Command (KLD), Washington, D.C. Compiled in 1959 by photogrammetric methods and from United States quadrangles 1:24,000, 1:25,000, 1:48,000, 1:50,000, and 1:62,500, 1927-57. Planimetry revised in part from aerial photographs taken 1944-54. Map field checked 1959. Revised by the U.S. Geological Survey 1969.

Location of geodetic control established by government agencies is shown on corresponding 1:250,000-scale Geodetic Control Diagram

LEGEND

Figures in red denote approximate distances in miles between stars

POPULATED PLACES

- Over 500,000
- 100,000 to 500,000
- 25,000 to 100,000
- 5,000 to 25,000
- 1,000 to 5,000
- Less than 1,000

ROADS

- Primary, all-weather, hard surface
- Secondary, all-weather, hard or improved surface
- Fair or dry weather, unimproved surface
- Light-duty, all-weather, hard or improved surface
- Interchange
- Route markers: Interstate, U.S., State

RAILROADS

- Normal gauge
- Narrow gauge
- Landplane airport
- Landing area
- Power line
- Marsh or swamp
- Interruption or dry stream
- Dry lake

BOUNDARIES

- International
- State
- County
- Park or reservation

WATER

- Water
- Woods brushwood

Scale 1:250,000

0 5 10 15 20 25 30 Statute Miles

0 5 10 15 20 25 30 Nautical Miles

CONTOUR INTERVAL 200 FEET

WITH SUPPLEMENTARY CONTOURS AT 100 FOOT INTERVALS

TRANSVERSE MERCATOR PROJECTION

BLACK NUMBERED LINES INDICATE THE 10,000 METER UNIVERSAL TRANSVERSE MERCATOR GRID, ZONE 11

MAGNETIC VARIATION FOR 1965 IS 14°51' (260 MILS) EASTERLY OVER THE ENTIRE AREA

LOCATION DIAGRAM

Map showing the location of the Salton Sea region within the United States, with labels for California, Arizona, and Mexico.

SECTIONIZED TOWNSHIP

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

GRID ZONE DESIGNATION

11S

TO LIVE A STANDARD REFERENCE ON THIS SHEET TO NEAREST 100 METERS

SAMPLE POINT: RIPLEY

1. Read letters identifying 100,000 meter square in which the point lies

2. Locate first VERTICAL grid line to LEFT of point and read LARGE figure labeling the line either in the top or bottom margin, or on the line itself

3. Locate first HORIZONTAL grid line BELOW point and read LARGE figure labeling the line either in the left or right margin, or on the line itself

4. Locate tenth from grid line to point

5. If reporting beyond 10' in any direction, prefix Grid Zone Designation, as:

11S091812

USGS AND HISTORICAL MAP

NOV 10 1968

RECD FILE COPY

STOCK NO. V502XN119